# MS Word Export To Multiple PDF Files Software - Please purchase license.SECTION 1 1.2 Results Summary University Union

#### ACM SURVEY RESULTS

The following homogeneous building material types were sampled as part of this survey conducted March 29, 30, and 31, 2004 and August 18, 2004. Results are summarized in the table below:

March 29, 30, and 31, 2004 Basement

## August 18, 2004

### University Union Building

MTL #	MATERIAL DESCRIPTION	LOCATION	F/NF <sup>1</sup>	COND. <sup>2</sup>	% ACM	# SAMP.	QUANTITY
01	Drywall system	2 <sup>nd</sup> floor by North service hall, at corner of kitchen hall	NF	Good	Drywall = ND JC = ND	3	N/A
02	4" Black cove base and mastic	2nd floor by North service hall, at corner of kitchen hall	NF	Good	Cove base = ND Mastic = ND	3	N/A
03	Carpet mastic, white leveling compound	Hallway north side corridor by side of kitchen area, by restrooms, dining area	F	Good	Mastic = ND Leveling cpd = ND	3	N/A
04	Wall plaster	Janitors' closet, men's restroom hall, women's restroom hall	NF	Good	ND	3	N/A
05	2' X 2' white pinhole, ceiling panel	Men's restroom and women's restroom	NF	Good	ND	3	N/A
06	Vent tape	Men's restroom	F	Good	ND	3	N/A
07	Acoustical spray-on	2 <sup>nd</sup> floor - dining room/area (3), game room, TV lounge, study area,	F	Good	2% Chrysotile	7	11,000 SF
08	Drywall system	3 <sup>rd</sup> floor - 309,310, 307 B	NF	Good	Drywall = ND JC = ND	3	N/A
09	4" black cove base and mastic	3 <sup>rd</sup> floor - women's restroom hall, 307 C, 307 A	NF	Good	Cove base = ND Mastic = ND	3	N/A
10	Acoustical spray-on	3 <sup>rd</sup> floor - 311, 309, 308, 310, 304, 302, by 307 A, 310 walkway	F	Good	2% Chrysotile	7	15,000 SF
11	2' X 2' white pinhole ceiling panel	3 <sup>rd</sup> floor -men's restroom, 307 A, 307 C, women's restroom	NF	Good	ND	3	N/A
12	Carpet mastic, white leveling compound	3 <sup>rd</sup> floor - 311, 315, by 303	NF	Good	Mastic = ND Leveling cpd = ND	3	N/A
13	Wall plaster	3 <sup>rd</sup> floor - by men's restroom, by women's restroom, by elevator	NF	Good	ND	3	N/A

\*Additional Sampling Jan. 2006 Drywall systems in Basement 102;107;104- no asbestos detected.

### ASSUMED ACM

,

The following materials were not sampled and have a

3

Panel board mastic	Room 101, 101A and 102	NF	Good	Assumed	0	24 SF
Mirror mastic	Men and women's room	NF	Good	Assumed	0	20 SF

Assumed Materials								
MATERIAL DESCRIPTION	LOCATION	F/NF <sup>1</sup>	COND. <sup>2</sup>	% ACM	# SAMP.	QUANTITY		
Firedoors/frames	Entrance and exit	NF	Good	Assumed	0	4		